

Des bâtiments en construction mixte acier-béton: Une alternative pour les entreprises générales de construction?!

Nachhaltige Gebäudelösungen in Stahl- und Verbundbauweise - eine Alternative für Generalunternehmer und Bauunternehmen?!

Univ.-Doz. Dr.-Ing. M. Schäfer









Application of steel and composite structures

High Rising Buildings

Industrial Buildings

Parking's

Bridges

Pylons, Towers

Chimney

Bunker, Tanks





Cranes and conveying plants






















Hubschrauberlandeplattform Universitätsklinikum Aachen Architekt: OX2architekten





Architectural Steel Structures

Advantages ... for architecture

- variety conceptions and forms
- innovative building structures
- elegant, transparent, lightweight and filigree structures
- small cross-sections
- optimal use in existing buildings
- good combinations with other materials such as concrete, glass and membranes, wood
- many options for installations




functional multi-storey office buildings




- Are Steel and Composite solutions also still interesting for functional ("ordinary") multi-storey office buildings?
- What does this mean for the general contractor or contractor and at least for the investor?



standard-solutions in steel and composite



steel and composite structures what does it mean for organization of building site



Advantages ... for production

- industrial production in workshop
- ▶ higher quality standards⇒ industrial standards
- production on basis of electronically controlled systems (CNC)
- better dimensional accuracy
- better conditions for welding process
- better operational safety
- independent of weather
- better waste management



steel and composite structures what does it mean for organization of building site




Example metal decking sheets:

- 850-1500m² of sheet by one lorry
- placing by hand
- low crane utilization




Advantages ... for construction site

- efficient time and cost management with just-in-time processes
- industrialized construction process for construction on site by using of "prefabricated" steel components
- less noise/waste on building site
- short construction period
- small site equipment (!)
- better coordination of logistics






Required preparation and planning phases for steel composite structures




Advantages of early design state

COST ALLOCATION OF CONSTRUCTION COSTS FOR OFFICE BUILDINGS



Advantages ... of early design state

- Agreement with architect and building installation engineers
- Solve of conflicts and problems for divers interfaces in an early state
- Planning reliability
- Time for optimization and preparation
- Including of 3-D drawings and BIM models
- ⇒ Reduction of construction costs!






Constraints in multi-storey buildings situation on construction site

Economic multi-storeys = mixed systems of concrete + steel composite elements

composite

foundation stiffening walls slabs (semi-precast or composite) columns (concrete or composite)

girders slabs (composite slabs) columns (steel or composite)





Problems on building site for mixed structures

- ☼ Often two different contractors for concrete and steel work
- © Coordination of an additional subcontractors
- Interface concrete work and steel work
- Coordination of logistics with several subcontractors
- © Reliability of construction schedules
- Availability of construction crane!
- © Connection steel to concrete
- © Connection often to labor intensive






optimization and simplification of steel-composite structures for multi-story buildings

Hypothese:

STEEL COMPOSITE STRUCTURE = PRE-FABRICATED STRUCTURE



- > simplification of interface between steel and concrete
- simplified connections between steel and concrete elements
 - plug-in connection (LEGO)
 - support consoles
 - easy compensation of tolerances
- simple placing of beams by construction crane without much bolting or any welding!










example of a standard office building



Surface:

 $A = 1093,4m^2$


 $A = 250m^2$

3 Levels:


 $A = 4030,2m^2$




example of a standard office building




solution with pre-stressed hollow core slab – without internal columns axe raster 13,50m/4,05m












solution with composite cellular beams – without internal columns axe raster 13,50m/4,05m




99





 $\theta_{crit.}$ = 617 C°




LUXEMBOURG


steelconstruction.info

IPE 450 - S460


solution with solid concrete slab axe raster 8,10m/7,75m/5,75m




solution with slim-floor beams and Cofraplus 220 slab



solution with primary and secondary composite cellular beam axe raster 8,10m/7,75m/5,75m







geometry:

L = 7,75/5,75/8,1m

 $h_{tot} = 560 mm$

 $h_{c} = 150 \text{mm}$

serviceability limit state

 $f_0 = 5,4/4,9Hz$


 $f_{o,q}^{o} = 5.0/4.6Hz (0.2q)$

w = < L/500


fire:

 $\theta_{crit.} = 592/583C^{\circ}$


steel ratio: 23,5 kg/m²



Fire protection of steel sections? fire design by natural fire




comparison of structure weight superstructure






comparison of building site logistics site traffic for structural work – superstructure/slabs





comparison of construction budget for slab systems of superstructure



43,74€

solution cellular beam solid concrete slab hc slimfloors e=8.1 hc =

=27cm



structural steel

■ prefabricated

elements

2.04 €

8,92€

10,26€

solution prefab.

concrte L=13,5m,

20,00€

0,00€

10,15 €

18,39€

L=13,5 e=2,7m

21,50€


Cellular e=4,05/8,01


hc=15cm

18,96€


30cm

influence of structure on facade





comparison of construction budget for slab systems considering the influence of structure on facade



advantages by the steel/composite construction method for the building owner and construction company

high degree of industrial prefabrication

high load capacity of the composite components

reduction of construction self-weight

integrated fire protection

weather independence

small site installation reduce of site-traffic

high flexibility of use by large spans and small component dimensions

short construction times, reducing the cost of capital

saving of natural recourses


reinforcement measures are simple to realize in case of later use changes

high dimensional accuracy, unrestricted interior fittings and installation works

sustainable structures with possibilities of recycling + re-use with financial returns



Journée Construction Acier 2015 mardi le 10 novembre, Luxembourg



merci de votre attention!!!

